BRUHAT BANGALORE MAHANAGARA PALIKE

SCHEDULE - B

Name of work:- Improvements of roads and drains in Jakkur Layout in ward No. 07-Byatarayapura, Kodigehalli Sub Division.

Sl. No.	Approved Qty.	Description	Unit	Schedule-B Rates KRIDL	
				In Figures	In Words
1	62.40	KSRB2-4. Refilling Available earth around pipe lines, cable in layers not exceeding 20cms in depth, compacting each deposited layer by ramming after watering with lean upto 50m and lift upto 1.5m including cost of all labour complete as per specifications., (Pg No.6, It No. 2.11)	cum	77.76	Rupees Seventy Seven and Seventy Six Paise Only
2	76.50	Refixing Stone slabs of drains and pointing in CM(1:3)(Pg No.25, It No. 5.33)	Sqm	78.84	Rupees Seventy Eight and Eighty Four Paise Only
3	848.88	KSRB 2-2.2:Earth work excavation for foundation of building, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in ORDINARY soil not exceeding 1.5m in depth including dressing the bottom and sides of pits and trenches , stacking the excavated soil clear from edges of excavation with lead upto 50m after breaking of clods complete as per specifications and direction of the Engineer-in-charge. Specification. No.KBS 2.1(b)/2.3.5. (P-5, It. No.2.1)	cum	159.84	Rupees One Hundred Fifty Nine and Eighty Four Paise Only
4	166.32	KSRB 4-1.3: Providing and laying in position plain cement concrete of nominal mix 1:4:8 using 40mm and down size graded granite metal machine mixed, conrete laid in layers not exceeding 15 cms. Thick well compacted in foundation and plinth, including cost of all materials labour, HOM of machinery, curing complete as per specification . (Pg.No.12, It.4.3)	cum	5070.6	Rupees Five Thousand Seventy and Sixty Paise Only
5	152.24	KSRB4-1.6: Providing and laying in position plain cement concrete of mix 1:2:4 with cement @ 240 kgs, with 20 mm and down size graded granite matel coarse aggregates @ 0.69 cum and fine aggragtes @ 0.459cum, machine mixed concrete laid in layers not eceeding 15 cms, thick well compacted, in foundation, plinth and cills including cost of all materials, labour HOM machinery curing complate as per specifications. (Page No. 12. Item No. 4.6)	cum	5490.72	Rupees Five Thousand Four Hundred Ninety and Seventy Two Paise Only
6	105.98	KSRB 4-48: Providing and laying in cement concrete using 20mm and down size granite coarse aggregates and fine aggregates of ready mixed concrete (RMC) for RCC works laid in 15cms thick layers and well compacted vibrating, curing, finishing with necessary cement mortar, with all lead and lifts etc., complate (exclusive of cost of steel and fabrication charges) (Pg No. 18, It No. 4.48)	cum	6332.04	Rupees Six Thousand Three Hundred Thirty Two and Four Paise Only
7	11.34	KSRB 5.3-1:Providing and constructing granite /trap/basalt size stone masonry in foundation with cement mortar 1:6, stone hammered dressed in courses not less than 20cms hign, bond stones at two m apart in each course including cost of materials, labour, curing etc., complete as per specifications.(P-235. Item No. 5.3	cum	3456	Rupees Three Thousand Four Hundred Fifty Six Only
8	405.00	KSRB 5.3-1:Providing ruled pointing of course stone masonry with cement mortar 1:3 20 mm deep, after raking joints to depth of 20 mm nicley lining, including cost of materials, labour, curing etc., complete as per specifications and directions of the engineer-in-charge (P-112, item No. 15.8)	Sqm	35.64	Rupees Thirty Five and Sixty Four Paise Only
9	7.25	KSRB 4-.9-2:Providing and fabricating TMT . Steel reinforcement for R.C.C. work including straightening, cutting, bending, hooking,placing in position, lapping and / or welding wherever required. tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design(laps and wasteage shall not measured and paid) cost of materials. labour. HOM of machinery complete as per specifications . (Page NO 17, Itm. NO. 4.46.2)	tonne	59327.91	Rupees Fifty Nine Thousand Three Hundred Twenty Seven and Ninety One Paise Only

No.	Approved Qty.	Description	Unit	Schedule-B Rates	
				KRIDL	
				In Figures	In Words
10	1009.23	SAB 4-6.4: Providing and removing centering, shuttering strutting, propping etc., and removal of form work for vertical surface such as walls at any thickness including attached pilasters, buttresses, plinth and string courses cost of all materials, labour complete as per specifications (Page no.14, Item No. 4.31)	Sqm	306.72	Rupees Three Hundred Six and Seventy Two Paise Only
11	556.25	Providing and fixing 10cms thick pre cast RCC covering slab using reinforced cement concrete M20 mix with stone aggregate 20mm and down size including centring shuttering reinforcement and bar bending machine mixed concrette laid in layers not exceeding 15 cm thick wellcompacted cost of all materials labour curing complete as per specfications (Data Rate Approved)	Sqm	1777.75	Rupees One Thousand Seven Hundred Seventy Seven and Seventy Five Paise Only
12	32.40	Providing and fixing 20 cm thick pre cast RCC covering slab using reinforced cement concrete M 20 mix with stone aggregate 20 mm and down size including centring shuttering reinforcement and bar bending machine mixed concrete laid in layers not exceeding 15 cm thick wellcompacted cost of all materials labour curing complete as per specification (Data Rate)	Sqm	4402.79	Rupees Four Thousand Four Hundred Two and Seventy Nine Paise Only
13	706.50	Vaccum De-watering with vaccum pump and suction mat and compaction with skin floater clubbed with floating disc including cost of generator, HOM of machinery screed vibaratory, power floater, blade and disc etc., with all leads and lift. (P171, It No. 22.7)	Sqm	97.2	Rupees Ninety Seven and Twenty Paise Only
14	96.24	Providing Groove cutting for width of 5mm to 10mm and depth 80mm - 100mm including cost of cutting machine, generator and HOM of machinery, inlcuding cost of blade, coolant etc., including cleaning of groove and providing sand and hot bitumen fillars and filler metal etc. including cost of all materails, labour, lead and lift charges and all other incidental charges as per drawing and as per specifications for concrete pavement (P-175, I No: 22.8.1)	m	124.2	Rupees One Hundred Twenty Four and Twenty Paise Only
15	40.00	Providing and fixing M S Grating 260 x 260 mm (pg no. viii, sl no.237, code no.0771)	nos	89	Rupees Eighty Nine Only
16	848.88	KSRRB M100-1 Loading and unloading of stone boulder/ stone aggregates/ sand/ kanker/ moorum. KSRRB M100-1:Placing tipper at loading point loading with front end loading, dumping turning for return trip, excluding time for haulage and return trip complete as per specification MORTH Chapter 1 (Page 118, item No. 17.1)	cum	94.82	Rupees Ninety Four and Eighty Two Paise Only

Signature of the Contractor

EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISION
BENGALURU-560 010

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92

24/X/16